

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21258-00-01
Spot: NESWNW Sec/Twnshp/Rge: 19-19S-13W
3784 feet from S Section Line, 4242 feet from E Section Line
Lease Name: WALLACE Well #: 2
County: BARTON Total Vertical Depth: 3461 feet

#112.48

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	758	0	w/unknown sxs cmt
PROD	5.5	3457	1541	w/unknown sxs cmt

Well Type: EOR UIC Docket No: E20159.1 Date/Time to Plug: 03/16/2010 1:00 PM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES CORPORAT Phone: (620) 793-2146

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 300# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded bottom and topped with 5 sxs cement.
Shot casing of at 1541' - tied onto casing - pumped 125 sxs cement with 300# hulls.
Pulled to 819' - pumped 40 sxs cement.
Pulled to 428' - pumped 40 sxs cement.
Pulled to 150' - circulated to surface with 55 sxs cement.
Pulled casing - hole stayed full.

Perfs:

INVOICED
DATE 4/05/10
INV. NO. 2010061023

RECEIVED
APR 05 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

MAR 31 2010

19-19-13W
NE SW NW

E 1865 KB CM 10/13/77 ^{CARD}ISSUED 4/27/78 IP D&A/ARB

API 15-009-21,258

[illegible]

8-5/8" 758, 5 1/2" 3457
DST (1) 2996-3031/OP 45", 30'M, SIP
442-146#/60", FP 32-32#, 40-40#
DST (2) 3248-60/OP 60", 300' GSY W W/
FEW SPKS O, SIP 382-324#/60", FP
89-138#, 146-178#
DST (3) 3340-62/OP 90", 1860' GIP,
180' HO&GCM, 30' O&GCM, SIP 720-690#
/60", FP NOT VALID, 210-210#
DST (4) 3364-85/OP 90", 270' VHOCM,
150' GIP, SIP 672-560#/60", FP 57-
79#, 91-113#
DST (5) 3386-3400/OP 60", 15' DM W/FEW
SPKS, SIP 24-24#/60", FP UNKNOWN
DST (6) 3457-65/OP 60", TOOL SLID TO
(OVER)

**INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS**