

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20037-00-00 #112.22
Spot: SWSENW Sec/Twnshp/Rge: 19-19S-13W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WALLACE Well #: 1
County: BARTON Total Vertical Depth: 3453 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	768	0	w/400 sxs cmt
PROD	5.5	3453	1641	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2010 1:00 PM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES CORPORAT Phone: (620) 793-2146

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 300# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded bottom and topped with 5 sxs cement.
Shot casing off at 1641' - tied onto casing - pumped 125 sxs cement with 300# hulls.
Pulled to 819' - pumped 40 sxs cement.
Pulled to 428' - pumped 40 sxs cement.
Pulled to 150 sxs cement - circulated to surface with 70 sxs cement.
Pulled casing - hole stayed full.

Perfs:

INVOICED
DATE 4/05/10
INV. NO. 2010061023

RECEIVED
APR 05 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

MAR 31 2010

CHIEF DRILLING CO., INC.

#1 WALLACE


19-19-13W
SW SE NW

Contr. CO TOOLS

Cty. BARTON

Geol.

Pool GREAT BEND TWN SITE



E. 1865 KB Cm. 3/30/67 Cp. 7/20/67 IPP 61 B0 + 19% W

TOP 3011-15

GRAV 28

NEW PAY ZONE

LOG Tops	Depth	Datum
TOP	2767	- 902
HEFB	3069	-1204
TOR	3085	-1220
BRLM	3169	-1304
LANS	3182	-1317
CONG	3404	-1539
ARB	3452	-1587
LTD	3455	-1590
TD	3457	-1592
DDTD	3468	-1603

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Csg. API 15-009-20,037
 8" 768/400 SX 5" 3453
 DST 2206-69/30", WB 9", 6' MD, BHP 45-20/30"
 FP 0-0#
 DST 3004-25/70", G/15", 1200 CL GSY OIL, BHP
 1094-1007#/30", FP 72-344#;
 DST 3060-3100/10", G/1" GAU 2420 MCFG 5",
 2060 MCFG 35", 1790 MCFG STAB 35", 210'
 WCM, BHP 1158-1118#/30", FP 600-400#
 DST 3169-90/40", 50' MD, BHP 179-168#/30",
 FP 56--56#;
 DST 3215-42/70", 290' THIN MD, 180' OCW,
 420' GSY OCW, BHP 736-720#/30", FP 168-
 408#;
 DST 3248-55/70", 680' CL OIL, 40' MDY OIL,
 BHP 608-352#/30", FP 152-280#;
 PST 3294-3315/25", 10' MD, BHP 35-22#/45",
 FP 22-22#

(CONT'D)