

181.68

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21036-00-00
Spot: SWNE Sec/Twnshp/Rge: 33-29S-34W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease Name: MLP LESLIE Well #: 1-33
County: HASKELL Total Vertical Depth: 5590 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5310		WITH 2 SX CMT
SURF	8.625	1760	0	WITH 650 SX CMT
PROD	5.5	4926	1767	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/19/2010 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMEC Company: CHESAPEAKE OPERATING Phone: (405) 935-4594

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2010 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5310' WITH 2 SX CMT. RIH W/TBG TO 1800'. COULDN'T FILL HOLE OR CIRCULATE, PUMPED 75 SX CMT. SDON. 3/22/10: RIH W/TBG. TAGGED TOC @ 1875'. POOH W/TBG TO 1800' & PUMPED 300# HULLS & 100 SX CMT. TAGGED TOC @ 1760'. PUMPED 300# HULLS & 75 SX CMT. 3/23/10: TAGGED TOC @ 1740'. PUMPED 400# HULLS & 50 SX CMT. TAGGED TOC @ 1615'. CIRCULATED HOLE WITH MUD & PUMPED 50 SX CMT AT 700'. PUMP 20 SX CMT AT 60'.

Perfs:

Top	Bot	Thru	Comments
5450	5460		
5410	5422		
5372	5380		

INVOICED
DATE 4/05/10
INV. NO. 2010061025

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Jack MacLashy
(TECHNICIAN)

RECEIVED
MAR 25 2010
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-24
APR 01 2010
CONSERVATION DIVISION
WICHITA, KS