

#115.05

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19056-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 36-20S-14W
660 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WRIGHT Well #: 5
County: BARTON Total Vertical Depth: 3540 feet

Operator License No.: 33725
Op Name: FOUNDATION ENERGY MANAGEMEN
Address: 14800 LANDMARK BLVD STE 220
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	370	0	w/100 sxs cmt
PROD	5.5	3525	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2010 11:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: KENT STRUBE Company: FOUNDATION ENERGY MANAGE Phone: (620) 786-4161

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 4% gel - 200# hulls - 13 sxs gel.
Perfed at 1600' - 825' - 385' - 150'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2010 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 825' - knocked off casing.
Ran tubing - went outside casing at about 800' - tried to get back in - could not get back in.
Ran tubing to 950' - pumped 50 sxs cement.
Pulled up to free pipe to 750' - pumped 315 sxs cement - cement circulated to surface.
Pulled tubing - tied to casing - pumped 100 sxs cement.
Max. P.S.I. 200#. Shut in.
Cement circulated out surface pipe and casing.

Perfs:

INVOICED
DATE 4/05/10
INV. NO. 2010061026

RECEIVED
APR 05 2010
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35874.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

MAR 30 2010

MAX COHEN

#5

WRIGHT

36-20-14W
NW SW SW

52

Contr. M. B. ARMER BARTON County

E. 1908RB Comm. 9-18-53 Comp. 12-4-53 IP 393 BOPD
PHY POT

Tops	Depth	Datum
HEEB	3120	-1212
BR LM	3233	-1325
LANS	3244	-1336
CONG	3480	-1572
ARB	3487	-1579
TD	3540	-1632

Casing
8" 370
5" 3525

CO 3540: SWB 12 BOPH/3 HRS

PRITCHARD SE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS