

9202

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-00247-00-00
Spot: W2NWSESE Sec/Twnshp/Rge: 36-18S-1W
1040 feet from S Section Line, 1156 feet from E Section Line
Lease Name: JONES Well #: 2
County: MCPHERSON Total Vertical Depth: 2833 feet

Operator License No.: 33409
Op Name: JONES, CHARLES
Address: 2504 MERIDIAN
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	169		115 SX
PROD	5.5	2832		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2010 10:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 654-8342

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 5 SXS CEMENT. CIRCULATE FROM 300' TO SURFACE OR BALE FLUID TO 300' AND DUMP SLURRY MIX TO FILL TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 03/02/2010 12:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2730' AND CAPPED WITH 5 SXS CEMENT. CUT PIPE AT 310' AND BALED FLUID TO 310' FEET. DUMPED 5 YARDS OF SLURRY MIX TO FILL TO SURFACE.

Perfs:

INVOICED
DATE 4/06/10
INV. NO. 2010061027

Remarks: CONCRETE PRODUCTS OF HILLSBORO TICKET #45424. TOTAL = 5 YDS SLURRY MIX 23 SX/YD SLURRY MIX

Plugged through: CSG

District: 02

Signed Greg Eves (TECHNICIAN)

RECEIVED
APR 02 2010
KCC WICHITA

JK