

107.48

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24301-00-00
Spot: S2NWSWSW Sec/Twnshp/Rge: 15-20S-11W
760 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DEBUSK Well #: 1
County: BARTON Total Vertical Depth: 3307 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	257	0	135 SX
PROD	4.5	3306	1641	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/19/2010 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/19/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off perfs and topped with 5 sxs cement.
Cut off casing at 1641' - pulled casing to 1631' - pumped 125 sxs cement with 300# hulls.
Pulled to 600' - pumped 50 sxs cement with 100# hulls.
Pulled to 200' - pumped 100 sxs cement with 100# hulls - circulated to surface.
Pulled casing - hole stayed full.

INVOICED
DATE 4/06/10
INV. NO. 200061028

RECEIVED
APR 05 2010
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

MAR 31 2010

L.D. DRILLING, INC
GREAT BEND, KS 67530

15-20 -11W
100'N, C W/2 SW SW

#1 DEBUSK

site: 2-3/4 S & 1-3/4 E OF ELLINWOOD, KS
contr: COMPANY TOOLS

city: BARTON
field: CHASE-SILICA

API 15-009-24301

geol:

fr date 01/21/88 spd date 01/25/88 drlg comp 01/30/88 card issued 03/02/88 last revised 03/02/88

ELV: 1770 KB LOG
tops.....depth/datum
HEEB.....2912 -1142
TOR.....2930 -1160
DOUG.....2946 -1176
BR LM3038 -1268
LANS.....3063 -1293
ARB.....3305 -1535
RTD.....3307 -1537

IP status:
OIL, P 114 BO & 20 BWPD, ARB OH 3306-3307 ,
CSG: 8-5/8" 257 / 135 SX, 4-1/2" 3306 / 175 SX
NO CORES
DST (1) 3073-3147 (LKC), / 45-45-45-45, 60' GIP, REC
165' SLI OIL & MCW ISIP 856# FSIP 791# IFP 35#
-54# FFP 72# -91#
DST (2) 3287-3307 (ARB), / 45-45-45-45, 900' GIP, REC
300' HGCO ISIP 801# FSIP 801# IFP 50# -71# FFP
95# -120#
MICT - CO, (ARB OH), AC 500 GAL, SWB DWN, GSO, POP,
P 114 BO & 20 BWPD, 2/5/88

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS