

96.49

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-19201-00-00
Spot: SWSSEW Sec/Twnshp/Rge: 25-19S-2W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: UNRUH A Well #: 3
County: MCPHERSON Total Vertical Depth: 2969 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		CIRCULATED
PROD	5.5	2944		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2010 10:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: SAND BACK TO 2894 & CAP W/5 SXS CEMENT. PUMP 35 SXS @ 450' AND CIRCULATE TO SURFACE FROM 250'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2010 4:00 PM KCC Agent: GREG EVES

Actual Plugging Report:
BROKE 2" PLASTIC TUBING OFF AT 600'. WAS UNABLE TO DRILL THE PLASTIC TUBING OUT AND SO WE PUMPED 95 SXS CEMENT WITH CALCIUM CHLORIDE THROUGH THE 5 1/2" CASING. RAN 1" DOWN TO 380' ON BACKSIDE AND PUMPED 100 SXS CEMENT. 3 HRS LATER WE HOOKED UP TO 5 1/2" AND PUMPED 150 SXS OF CEMENT W/CALCIUM CHOLORIDE. RAN 1" TUBING DOWN BACKSIDE TO 380' AND PUMPED 91 SXS CEMENT TO CIRCULATE TO SURFACE. (5 1/2" ALSO CIRCULATED TO SURFACE)

Perfs:

INVOICED
DATE 4/06/10
INV. NO. 2010061029

Remarks: COPELAND CEMENTING TICKET #34465 TOTAL = 436 SXS 60/40 4% GEL
Plugged through: TBG

District: 02

Signed Meg Eves
(TECHNICIAN)

RECEIVED
APR 02 2010
KCC WICHITA

JK