

\$113.⁷⁸

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22374-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 13-19S-14W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ESSMILLER Well #: 2
County: BARTON Total Vertical Depth: 3501 feet

Operator License No.: 6496
Op Name: STEPHENS, FAYE ESTATE DBA I & F OI
Address: 33117 SE BOOTH RD
KINCAID, KS 66039

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	804	0	w/unknown sxs cmt
PROD	4.5	3492	2035	75.5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2010 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: IRA STEPHENS III Company: I & F OIL AND FARM Phone: (620) 496-6638

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 2035'.
Pulled casing to 1576' - pumped 120 sxs cement with 250# hulls.
Pulled to 825' - pumped 40 sxs cement with 50# hulls.
Pulled to 450' - pumped 50 sxs cement with 50# hulls.
Pulled to 150' - circulated to surface with 75 sxs cement and 50# hulls.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3362	3368		
3346	3350		

INVOICED
DATE 4/06/10
INV. NO. 2010061032

RECEIVED
APR 05 2010
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

MAR 31 2010

IRA STEPHANS JR

13-19-14W

RR #2

#2 ESSMILLER

SW SW SW

KINCADE, KS 66039

CONTR EMPHASIS OIL OPER

CTY BARTON

GEOL LEWIS CHUBB

FIELD ESS

E 1879 KB CM 5/22/81 CARD ISSUED 9/3/81 IP P 30 BOPD, NW

1871 GL

LKC 3346-3368 OA

API 15-009-22,374

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
		787	+1092
ANH		3206	-1327
LANS		3421	-1542
RKC		3446	-1567
CONG			
RTD		3501	-1622

8 5/8" 804; 4 1/2" 3492

NO DSTS
MICT - CO, PF(LKC) 3346-50, 3362-68,
AC200G, POP, P 30 BOPD, NW

NOTE: WAS #1 ESSMILLER

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS