

\$127.89

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24384-00-00
Spot: SESWNW Sec/Twnshp/Rge: 19-20S-15W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: IANNITTI Well #: 2
County: BARTON Total Vertical Depth: 3935 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3820		
SURF	8.625	343	0	165 SX
PROD	4.5	3934	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2010 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 200# hulls - 10 sxs gel.
Well has a port collar - cement to 400'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3700' - pumped 10 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled to 1600' - pumped 90 sxs cement with 100# hulls.
Pulled to 700' - circulated cement to surface with 110 sxs cement.
Tied to surface pipe - pumped 15 sxs cement.
Max. P.S.I. 900#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3816	3818		

INVOICED
DATE 4/06/10
INV. NO. 2010061033

RECEIVED
APR 05 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37136.

Plugged through: CSG

District: 04


Signed Bruce Rodie
(TECHNICIAN) CM

MAR 30 2010

STATE KANS COUNTY BARTON
 FIELD PAWNEE ROCK (ARBUCKLE)
 OPER WOODMAN & IANNITTI DRLG
 WELL 2 IANNITTI OIL CO
 API 15-009-24384-0000
 SPUD 08/19/1989
 DTD 3935 LTD FTD ARBUCKLE

19-20S-15W
 SE SW NW
 2970FSL 4290FEL SEC

WELL CLASS DO
 STATUS OIL
 COMP 10/03/1989
 PBTD



LOC 3 1/4 MI NW PAWNEE ROCK, KS

Petroleum Information
 CORPORATION

IP IPP 20 BOPD 40 BW GTY 40 NATURAL
 PROD ZONE: ARBUCKLE 3816-3825

EL: 2113 KB 2108 GR

CSGS: 8 5/8 @ 343 W/ 165 SACKS
 4 1/2 @ 3934 W/ 100 SACKS
 DV TOOL @ 1098 W/300 SX
 TBGS: 2 7/8 @ 3812
 DRLG COMP 8/25/89 RIG REL 8/25/89

LOG TOPS:
 STONE CORRAL 1123 +990
 BSE STN CORRAL 1150 +963
 HEEBNER 3426 -1313
 TORONTO 3443 -1330
 DOUGLAS 3454 -1341
 BROWN LIME 3513 -1400
 LSG-KANSAS CITY 3525 -1412
 BSE KANSAS CITY 3753 -1640
 ARBUCKLE 3808 -1695
 TD 3935 -1822

DSTS: DST 1 3809-3817 ARBUCKLE
 REC 1140 FT GCO 120 FT WTR
 INIT OP 30M IFP 164 FFP 141
 FINAL OP 30M IFP 199 FFP 282
 ISIP 955 45M FSIP 931 45M IHP 1923
 FHP 1923

PERFS: ARBUCKLE PERF W/ 3/FT 3816-3825
 DID NOT TREAT

NO CORES

OPER ADDRESS: BOX 308, GREAT BEND, KS 67530
 CONTR: WOODMAN & IANNITTI

GEOLOGIST: TODD MORGENSTERN

KS 15-010290

Copyright 1990 Petroleum Information Corporation