

135.69

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21358-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 27-10S-23W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: GEIST Well #: 1  
County: GRAHAM Total Vertical Depth: 4175 feet

Operator License No.: 30553  
Op Name: UNREIN, GLENN DBA UNREIN OIL CO  
Address: 300 W 40TH ST  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	244	0	w/200 sxs cmt
PROD	4.5	4025	0	w/200 sxs cmt
RBP		3660		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/18/2010 2:30 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: OZZIE Company: UNREIN OIL COMPANY Phone: (785) 628-6231

Proposed Plugging Method:	Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls. CIBP at 3660'. Shoot perms at 1100' and 230'. Tried to drill out with pump and swivel - could only get to 1700'. Almost had bit stuck coming out. Mudded up and tried still the same.
---------------------------	---

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/18/2010 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1647' - pumped 40 sxs cement.  
Pulled tubing to 1018' - pumped 40 sxs cement.  
Pulled tubing to 521' - pumped 40 sxs cement - good circulation of cement.  
Tied onto 4 1/2" - pumped 50 sxs cement - circulated cement out backside - shut in.  
Squeezed 4 1/2" with 300# P.S.I. Shut in.

Perfs:

Top	Bot	Thru	Comments
3805	3807		L-KC

INVOICED

DATE 4/06/10  
INV. NO. 201006034

RECEIVED  
APR 05 2010  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3754.

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

CM

MAR 31 2010

