

# 95.06

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20944-00-00  
Spot: NE Sec/Twnshp/Rge: 15-35S-40W  
3960 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: GERBER D Well #: 1H  
County: MORTON Total Vertical Depth: 2925 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: PO BOX 1330  
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	609		WITH 390 SX CMT
PROD	5.5	2925	718	WITH 255 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2010 2:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CHECK TD W/WIRELINE. 25 SX CMT ON TOP OF FILL UP. 1700' WITH 25 SX CMT. MUD SPACER WITH HULLS BACK TO 700'. SHOOT CASING. 50 SX CMT AT 650'. 10 SX CMT AT SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 03/26/2010 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAK BETWEEN 1302-1372'. TOP OF FILL @ 1283'. PUMP 200# HULLS & 50 SX CMT AT 1280'. TAGGED TOC @ 804'. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2558	2675		

INVOICED  
DATE 4/09/10  
INV. NO. 2010061036

RECEIVED  
APR 07 2010

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.  
Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
MAR 31 2010  
KCC DODGE CITY