

\$ 209.63

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21659-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 7-34S-39W
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: HJV CORNELL UNIV C Well #: 1
County: MORTON Total Vertical Depth: 6450 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4760		
SURF	8.625	1730		WITH 520 SX CMT
PROD	5.5	5012	1637	WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/22/2010 8:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT & HULLS ON BOTTOM. PLUG AT 1780' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 03/22/2010 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4760'. PUMP 25 SX CMT & HULLS TO 1730'. TAG CMT AT 1637'. RAN 5 1/2" TO 1637'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4802	4818		

INVOICED
DATE 4/09/10
INV. NO. 2010061036

RECEIVED
APR 07 2010

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

KCC WICHITA

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
MAR 25 2010 *MR*

KCC DODGE CITY

[Signature]
FORM C-2/3