

#172.25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20288-00-00
Spot: SESWNE Sec/Twnshp/Rge: 11-16S-43W
2992 feet from S Section Line, 1673 feet from E Section Line
Lease Name: EDSALL Well #: 2-E
County: GREELEY Total Vertical Depth: 5300 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5100		WITH 2 SX CMT
SURF	8.625	616		WITH 425 SX CMT
PROD	4.5	5294	0	WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/11/2010 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN LOEB Phone: (618) 943-2227

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2010 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 5100' & 2 SX CMT. 2ND PLUG TEST CASING TO 700 PSI. RAN BOND LOG. FROM 2850'-800' FOUND TOOL @ 1754' BUT NO CMT. SHOT 3 HOLES @ 2790' THEN RAN TBG TO 2790' & PUMPED 40 SX CMT & 100# HULLS. WAIT ON CMT 2 HOURS. TOC @ 2200'. 3RD PLUG PERFORATE 3 HOLES @ 1823'. ESTABLISH RATE, PUMP 50 CMT, 5 BALL SEALERS, 30 SX CMT, & DISPLACE WITH 21 BBLs WATER. SHUT IN @ 1500 PSI. 4TH PLUG PERFORATE @ 630'. ESTABLISH RATE, CIRCULATE CMT TO SURFACE WITH 170 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5166	5183		

INVOICED
DATE: 4/09/10
INV. NO. 2010061037

RECEIVED
APR 07 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
MAR 25 2010
KCC DODGE CITY

Signed Ken Jehlik
(TECHNICIAN)

Form CP 20