

#109.36

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07024-00-00
Spot: NENENW Sec/Twnshp/Rge: 25-16S-12W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MARTHA M CASE Well #: 1
County: BARTON Total Vertical Depth: 3365 feet

Operator License No.: 9951
Op Name: KRIER, KIRBY OIL, INC.
Address: 1043 NE 80TH RD
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	425	0	210 SX CMT
PROD	5.5	3351	0	100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2010 10:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: KIRBY KRIER Company: KRIER, KIRBY OIL, INC. Phone: (620) 562-7637

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel.
Perf: 1250' - 830' - 400'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2010 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3000' - pumped 16 sxs gel - followed with 50 sxs cement and 250# hulls.
Pulled tubing to 1250' - pumped 50 sxs cement with 50# hulls.
Pulled tubing to 600' - pumped 70 sxs cement - circulated out the backside - shut in.
Pumped 40 more sxs cement and circulated out the Braden head.
POOH. Filled casing with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3351	3365		

INVOICED

DATE 4/09/10
INV. NO. 2010061038

RECEIVED
KANSAS CORPORATION COMMISSION

APR 06 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3881.

Plugged through: TBG

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

APR 02 2010

GULF OIL CORP

#1

MARTHA M CASE

25-16-12W
NE NE NW

Contr.

BARTON

County

E 1919 Comm. 10-10-43 Comp. 11-5-43 IP 655 BOPD


Tops	Depth	Datum
ANHY	815	
LANS	3097 or 3079	
ARB	3350	
TD	3365	

Casing

8" 420

5" 3351

2150' OIH/12 hr



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS