

\$100.75

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20639-00-00
Spot: NE Sec/Twnshp/Rge: 17-20S-40W
3960 feet from S Section Line, 1320 feet from E Section Line
Lease Name: WALLACE UNIT Well #: 1
County: GREELEY Total Vertical Depth: 3100 feet

Operator License No.: 3555
Op Name: SODERSTROM, GLEN S.
Address: 429 COUNTRY SIDE LN
RICHARDSON, TX 75081

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264		WITH 175 SX CMT
PROD	5.5	3099	0	WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/16/2010 12:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. GEL TO 900' & CMT TO 0'.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2010 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SQUEEZED @ 1700' WITH 335 SX CMT. 1/25/96: PUMP 100 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PUMP 250# HULLS & 25 SX CMT @ 2881'. 1ST PLUG PUMP 19.5 BBL MUD SPACER & 25 SX CMT AT 1500'. 2ND PLUG PUMP 10 BBL MUD SPACER & 100 SX CMT FROM 900' TO 0'. SHUT IN PRESSURE 700#. FILL ANNULUS WITH 2 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2854	2858		5 SHOTS
2848	2851		4 SHOTS
2816	2881		6 SHOTS

INVOICED
DATE 4/09/10
INV. NO. 2010061040

RECEIVED
APR 07 2010
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED
MAR 25 2010
KCC DODGE CITY

Form CP-223