

\$ 117.75

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20419-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 5-1S-26W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ATHERTON Well #: 5
County: DECATUR Total Vertical Depth: 3623 feet

Operator License No.: 32628
Op Name: QUANTUM OPERATING COMPANY
Address: PO BOX 3029
DENVER, CO 80201

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264	0	w/190 sxs cmt
PROD	4.5	3623	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2010 9:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: JIM SMITH Company: QUANTUM OPERATING COMPAN Phone: (785) 216-0833

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2010 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3350' - pumped 100 sxs 60/40 pozmix - 4% gel with 225# hulls.
Pulled tubing to 1900' - pumped 75 sxs 60/40 pozmix - 4% gel with 150# hulls.
Pulled tubing to 700' - pumped 40 sxs 60/40 pozmix - 4% gel with 75# hulls to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 110 sxs 60/40 pozmix - 4% gel with 150# hulls.
04/01/2010 - Topped off 4 1/2" casing with 15 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3586	3594		

INVOICED
DATE 4/09/10
INV. NO. 2010061041

RECEIVED
KANSAS CORPORATION COMMISSION
APR 06 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT CEMENTING COMPANY-TICKET #17550.
Plugged through: TBG

District: 04 Signed Pat Bedore
(TECHNICIAN) CM

APR 02 2010

TRACEY ENTERPRISES, INC.
407 W. COMER, OBERLIN, KS.


#5 ATHERTON

5-1-26W
SW NW SW

CONTR DRELLING OIL, INC. CTY DECATUR

GEOL JERRY GREEN FIELD BLEES

E 2509KB CM 3/25/78 CARD ISSUED 12/29/78 OIL WELL
TNTV UNKNOWN



API 15-039-20,419

LOG	TOPS	DEPTH	DATUM
TOP		3111	-602
HEEB		3238	-729
LKC		3278	-769
BKC		3490	-981
REAG		3586	-1077
PBTD		3623	-1114
TD		3625	-1116

8 5/8" 264/190sx, 4 1/2" 3623/150sx
NO DST
OIL WELL-(FORMATION & INTERVAL UNKNOWN)
TIGHT HOLE - NO OTHER INFO TO BE RE-
LEASED BY OPERATOR AT PRESENT TIME.
WILL RELEASE INFO WHEN AVAILABLE.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS