

15-065-20596-0000

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 2 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 KSB & T Building, Wichita, Kansas.

Lease Name: Waldt Well No. 1

Location: NW-NW-SW Sec. 18 Twp. 18 Rge. 10 (E)(W) 25

County: Graham Total Depth 4025' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

262'--8 5/8" Surface casing, cement circulated with 175 Sx.

Top of Dakota section @ 1015'.

Circulate hole with heavy mud. Pull DP to 1240' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Fike  
Conservation Division Agent