

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this
date requested permission to plug the following described well:Mr. Rice guarantees payment of the plugging fee.Operator's full Name: Dorchester Exploration, Incorporated,Complete Address: 1204 Vaughn Building, Midland, Texas.Lease Name: Beard Well No. 1Location: 1150' FSL & 1150' FEL - Sec. 36 Twp. 20 Rge. (E)(W) 41County: Greeley Total Depth Oil WellGas Well Input Well SWD Well D & A X Lost HoleMr. Rice was instructed to plug the well as follows:345'--10 3/4" Surface casing, cement circulated with 300 Sx. (9" Hole).
Top of Dakota section @ 950'.Circulate hole with heavy mud. Pull DP to 1175 and displace 140 Cu. Ft.
cement thru DP. Pull DP to 340' and displace 40 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 20 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent