

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-8-1971
FEB 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herman Johnson of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Derrick-American Oil, Incorporated,

Complete Address: 355 R. H. Garvey Building, Wichita, Kansas.

Lease Name: Brungardt Well No. A-5

Location: SW-NW-SW Sec. 22 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 335' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Johnson was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated.

Lost circulation @ 255', unable to regain. Fluid level standing @ 75'.

I gave Mr. Johnson two alternatives either to push a plug to 250' and build a rock and sand bridge to 225' then circulate heavy gel mud from top of bridge to cellar then spot 20 Sx. cement @ 225' and 10 Sx. @ 30' or balance 30 Sx. hot cement across surface casing seat, fill hole to 30' with heavy gel mud and 10 Sx. cement to bottom of cellar. He chose the second.

Very truly yours,

W. L. Dickole
Conservation Division Agent