



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
4-26-1971
APR 26 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Richard Foley of American Drilling Co., Ltd., has this date requested permission to plug the following described well:

Mr. Foley guarantees payment of the plugging fee.

Operator's full Name: American Drilling Company, Ltd.

Complete Address: 360 Sutton Place, Wichita, Kansas.

Lease Name: Knoll Well No. 3

Location: CE/2-W/2-SE Sec. 22 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4020' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Foley was instructed to plug the well as follows:

204'--8 5/8" Surface casing, cement circulated with 205 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent