

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
8-26-1966  
AUG 26 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc., has this

date requested permission to plug the following described well:

Okmar Oil Co.

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Seraphine Well No. 1

Location: CSE-SW Sec. 22 Twp. 10 Rge. (E)(W) 25

County Graham Total Depth 4067 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

242'--8 5/8" Surface casing, cement circulated with 185 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	210'	with $\frac{1}{4}$ sk. hulls &
			20 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			10 Sx. cement.

Very truly yours,

Conservation Division Agent