

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 14-179-20,786

LEASE NAME Deines

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1
165' S of SE NE SW
SPOT LOCATION

SEC. 3 TWP. 10S RGE. 26W (E) or (

LEASE OPERATOR DaMar Resources, Inc.

COUNTY Sheridan

ADDRESS Box 70 Hays, Kanss 67601

Date Well Completed

PHONE # (913) 625-0020 OPERATORS LICENSE NO. 9067

Plugging Commenced 3-7-86

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-21-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4130'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	290'	none
				4-1/2"	4129'	1423'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3850' and 5 sacks cement. Shot casing @2892', 2508', 2017', 1798', 1605', 1485', 1423' and pulled a total of 34 joints (1423') of 4-1/2" casing. Plugged surface with 4 hulls and 200 sacks ecanolite.
Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 25th day of March, 1986

Irene Hoover
Notary Public
STATE CORPORATION COMMISSION

My Commission expires:



MAR 27 1986

CONSERVATION DIVISION

Form CP-4
Revised 01-84