

15-179-20013-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Sheridan County, Sec. 12 Twp. 10 Rge. 26 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW-NW-NE

Lease Owner Leo J. Dreiling Oil Company

Lease Name Mader Well No. #1

Office Address Victoria, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-14 19 67

Application for plugging filed 5-14 19 67

Application for plugging approved 5-14 19 67

Plugging commenced 5-14 19 67

Plugging completed 5-14 19 67

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE CASING				8 5/8"	197'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st. plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 180' where 2nd. plug was set using 20 sacks cement. Rotary mud was used to fill hole to a depth of 40' where 3rd. plug was set using 1/4 sack hulls and cementing to bottom of cellar.

RECEIVED
5-17-67
MAY 17 1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.

Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of May, 19 67

My Commission expires September 19, 1970

Joseph A. Hess Notary Public.

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Victoria, Kansas	Sec.	12	Twp.	10	Eng.	26
Farm	Mader No. 1	Location	NW-NW-NE				
Total Depth	4034'	County	Sheridan				
Comm.	5-9-67	Comp.	5-11-67				
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas	Elevation:	2547'	K.B.			
			2544'	D. F.			
			2542'	G. R.			
	Casing Record	Cement Record	Production: D & A				
	197' 8 5/8"	150 Sack Cement					

Figures Indicate Bottom of Formations

0'	40'	Surface Soil & Clay
40'	110'	Clay & Sand
110'	136'	Shale
136'	197'	Shale
197'	1220'	Shale
1220'	1560'	Shale
1560'	1700'	Gyp & Shale
1700'	1740'	Shale & Redbed
1740'	1934'	Sand
1934'	1975'	Shale & Redbed
1975'	2164'	Shale & Redbed
2164'	2206'	Anhy.
2206'	2415'	Shale & Shells
2415'	2645'	Lime & Shale
2645'	3005'	Lime & Shale
3005'	3235'	Lime & Shale
3235'	3325'	Shale & Lime
3325'	3575'	Lime & Shale
3575'	3730'	Lime & Shale
3730'	3842'	Lime & Shale
3842'	3895'	Lime
3895'	4005'	Lime
4005'	4034'	Lime
4034'	∅.D.	

RECORDED
MAY 17 1967
OCCUPATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Mader #1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 16th day of May 1967.

Joseph A. Hess
JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970