

Operator & Address: Muttler Dale

Lic.# 30606 Contact Person: Mark Robben Phone # 785-735-4621

Lease Name & Well # Bunker # 2 API # or Spud Date: 15-195-21,662-0000

Location: G E/2 NE SW 4 Sec: 24 Twp: 12 Rge: 22 E 18 County: \_\_\_\_\_

1980' feet from the North / South Line, 2970 feet from the East / West Line of SE 1/4 section.

Purpose of Pit: Work Over Depth to Ground Water: \_\_\_\_\_

Nature of Fluids: KC & Topeka workover fluids salt water, cement

Construction: Dirt, Width: 10, Length: 15, Depth: 6 bbl capacity: 80 BBL

Liner Specifications: Plastic

This lease produces from the following formation(s): KC & Topeka

Date of Verbal Permit: 3-9-2008, KCC Agent: Pat Tread

To save paperwork, copy this form after completion of the first 11 lines. Use copy for closure form.

Dates Pit Used: From 3-9-08 To 3-16-08 Date Water Hauled: \_\_\_\_\_

Proposed Closing Procedure / Actual Closure information: \_\_\_\_\_

Pit must be closed in \_\_\_\_\_ days. \_\_\_\_\_

(signature) (date)

\*\*\*\*\* KCC USE ONLY \*\*\*\*\*

Groundwater Sensitive Area YES ( ) NO ( ); Field Inspection Date: \_\_\_\_\_, Agent: \_\_\_\_\_

Chloride of Water in Pit: \_\_\_\_\_, Date Collected: \_\_\_\_\_

\_\_\_\_\_ feet to nearest Water Well. Depth of Water Well: \_\_\_\_\_, Application Tabulated

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 10 2008  
CONSERVATION DIVISION  
WICHITA, KS

HESS OIL COMPANY &  
JOHN JAY DARRAH  
405 CENTURY PLAZA BLDG.  
WICHITA, KS 67202

REPLACEMENT CARD

#2 BUNKER

24-12-22W  
C E/2 NE SW

CONTR MALLARD DRILLING CO. CTY TREGO

GEOL BETH FUHR & JIM HESS FIELD SHERFICK SO. EXT  
(1/4 S)

ELV 2349 KB SPD 4/9/85 CARD 6/20/85 IP P 35 BOPD, NW  
2341 GL LKC 3674-3676

API 15-195-21.662

LOG	Tops	Depth/Datum	
ANH		1769 + 580	8 5/8 " 304 / 200SX, 5 1/2 " 4058 / 200SX
TOP		3378-1029	DST (1) 3590-3690 (TOR) / 30-30-45-45, REC 30' SOC GSY M, 120' GSY OCM, 240' HG & OCM, SIP 646-657#, FP 156-160 / 167-178#
HEEB		3596-1247	DST (2) 3696-3712 (LKC) / 30-30-10-0, REC 40' M, SIP 780#- NO FSIP, FP 44-55# / NO FFP
TOR		3620-1271	DST (3) 3965-3995 (MARM) / 30-45-10-0, REC 8' SOCM, SIP 1046#-NO FSIP, F33-33 / 44#-NO FFP
LANS		3632-1283	MICT - CO, PF (LKC) 3709-11, AC 300G, SWB LD, NS, SET PLUG AT 3698', PF (LKC) 3674-76, AC 1500G, SWB 7 BFPH (70% OIL), T&R, POP, P 35 BOPD, NW, 6/10/85
KC		3672-1323	
MARM		3962-1613	
ARB		NOT RPTD	
PBTD		3698-1349	
RTD		4060-1711	
LTD		4063-1714	

INFO RELEASED: 9/19/85 - ORIGINALLY FIRST REPORTED AS THE  
#1 BUNKER

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 10 2008

CONSERVATION DIVISION  
WICHITA, KS