

3 030681

7-22-87

15-073-01064-00-00

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A.

ANG EX

SENE NE, SEC. 10, T 26 S, R 12 WE

TECHNICIAN'S PLUGGING REPORT

Operator License # 5446

Operator: Ben Giles

Name &

Address 321 E. William

Wichita, Kansas

4290 feet from S section line

330 feet from E section line

Lease Name Lindemood Well # 1

County Greenwood

56.23

Well Total Depth 1730 feet

Conductor Pipe: Size feet

Surface Casing: Size 7" feet N/A

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hydrocarbon Exploration License Number 3302

Address Madison, Kansas 66860

Company to plug at: Hour: 8:00 am Day: 20 Month: 7 Year: 1987

Plugging proposal received from Bruce Meyer

(company name) Hydrocarbon Exploration (phone)

were: 50' cement plug on TD.

50' cement plug at 700'

250' to surface with cement.

Plugging Proposal Received by Dave Monical
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 7:00 pm Day: 22 Month: 7 Year: 1987

ACTUAL PLUGGING REPORT Perf. from 1688' to 1694', dumped sand to 1680' and 6 sacks

cement with dump bailer. Ripped 4 1/2" at 900', set br. at 700' and dumped

6 sacks cement with dump bailer. Pulled 4 1/2", set br. at 275' and filled

to surface with cement.

RECEIVED

STATE CORPORATION COMMISSION

08-07-87

AUG 7 1987

CONSERVATION DIVISION

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 8-10-87

INV. NO. 17794

Signed

(TECHNICIAN)

FORM CP-2/3
Rev. 01-84