

To: 1 052124 4-15 API NUMBER 15- 033-20,919 - 00-00
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION E/2 SE SW SW, SEC. 36, T 32 S, R 19 W/E
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License / 3882
Lease Name Colter Well / 36-13

Operator: Samuel Gary Jr. & Associates
Name & Address: 1670 Broadway, Ste. 3300
Denver, CO 80202
County Comanche 200.79
Well Total Depth 6178 feet
Conductor Pipe: Size 20 feet 60
Surface Casing: Size 8 5/8 feet 670

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address Medicine Lodge, KS

Company to plug at: Hour: 11:30 a.m. Day: 15 Month: 4 Year: 19 97

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-886-5665

Work: 5 1/2" at 6178' w/100 sx cement, PBD 6133', Perfs at 6083-86, 6078-87, 6058-70'

1st plug set CIBP at 6000' and dump 2 sx cement on top.

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:35 p.m. Day: 15 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5978' with 2 sx cement on top,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3900' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

DATE 4-17-97 Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 47967
FORM CP-2/3
Rev. 01-84

APR 17 1997
10:39 AM
04-17-97