

To: 1052106 2-5
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-145-20,035-00-01
NW SW SE, SEC. 23, T 23 S, R 16 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 31649
Operator: Ward Feed Yard, Inc.
Name: Ward Feed Yard, Inc.
Address: P.O. Box H
Larned, KS 67550

Lease Name Schartz Well # 1
County Pawnee 137.15
Well Total Depth 4220 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well Gas Well ^{APIEX} Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1 p.m. Day: 5 Month: 2 Year: 1997

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-687-3361

Work: 4 1/2" at 4202' w/100 sx cement, Perfs at 4096-4101'

1st plug sand back to 4040' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 5 Month: 2 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 4040' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 300 psi and shut in 100 psi.

Planned to pump 125 sx cement on top, but blew a hole in the 8 5/8".

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (if additional description is necessary, use BACK of this form.)
observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE _____
INV. NO. 47595

RECEIVED
KANSAS CORP COMM
1997 FEB 18
3:24
02-18-97