

1 040862

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-30

API NUMBER 15- 1965 15-033-00110-00-00

S/2 SE NW, SEC. 16, T 35 S, R 16 W, XX
2970 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9723

Lease Name McMoran Well # 1

Operator: DoMar Oil & Gas, Inc.

County Comanche

Name & Address P.O. Box 238

Well Total Depth 5865 190.61 feet

Liberal, KS 67905-0238

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9:30 a.m. Day: 30 Month: 6 Year: 1994

Plugging proposal received from Kirby Lillard

(company name Sargent's Casing Pulling (phone) 316-624-7455)

vers: 4 1/2" at 5865' w/225 sx cement, Perfs at 4923-5024'

1st plug pump 20 sx cement and 2 sx hulls on bottom,

2nd plug pump 50 sx cement at 1000',

3rd plug pump 40 sx cement at 380',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 30 Month: 6 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 200 lbs. hulls and 20 sx cement.

Stopped plug at 4800'.

2nd plug loaded hole with drilling mud and spotted plugs through 4 1/2" casing with 50 sx cement

at 1000'.

3rd plug at 380' with 40 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 08 1994

Remarks: Used common cement by Sargent's. Recovered 3444' of 4 1/2" casing.
(If additional description is necessary, use BLA on reverse of this form.)

INVOICED

DATE 7-11-94

INV. NO. 40804

6-30

Signed Stephen J. Pfeifer
(TECHNICIAN) RWL

(did ~~not~~ observe this plugging.)