

6 030695

API NUMBER 15-179-20,786-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

165'S
SENECA SEC. 3, T. 10 S, R. 26 W E

1485 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name DEINES Well # 1

Operator: DAMAR RESOURCES INC.

County SHERIDAN 134.23

Name & Address 217 E. 32ND. BOX. 70

Well Total Depth 4130' feet

HAYS, KANSAS

Conductor Pipe: Size _____ feet

67601

Surface Casing: Size 8 5/8 feet 290'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS 67524

Company to plug at: Hour: PM Day: 12 Month: 3 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING. (phone) _____

were: 8 5/8 SET @ 290' w/ 175 SX. 4 1/2" SET @ 4129' w/ 240 SX. PBTD 4084'

PERFS 3900' TO 4068 @ INTERVALS ORDER SAND & COM. CNT. BOTTOM PLUG.

SHOOT & STRIP PIPE ORDER 200 SX. Econo-Lite 4 SX. HULLS

ALLIED CNT. CO. JOE NEUMAN WATER TRUCKS

STATE CORPORATION COMMISSION

APR 7 1986

Plugging Proposal Received by Carl Goodrow

CONSERVATION DIVISION
(TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 PM Day: 12 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3850' SPOT 4 SX. COM. CNT. ON SAND

w/ BAILER. SHOT & STRIPPED 1400' OF 4 1/2".

HOOK ON TO 8 5/8 MIX. & Pump 4 SX. HULLS & 200 SX. ECONO-LITE AFT

PRESSURED WHEN WE HIT FLUID AND MAINTAINED PUMP PRESSURE

TO END OF PLUG. CEMENT REMAINED AT GROUND LEVEL w/NO VAC.

CEMENT CONTINUED TO SWELL. PLUG. COMPLETE

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
APR 8 1986

DATE _____

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 13329