

4-042033

E-24,676

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-20,835-0000

NE SW SE _____ / 4 SEC. 03, 10 S, 26 W
990 feet from S section line
1650 feet from E Section line

Operator license# 32322

Lease: Ziegler Well # 6

Operator: Dennis F. Roberts

County: Sheridan 133,58

Address: P.O. Box 1252
Hays, Kansas 67601

Well total depth 4110 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 303 Feet
W/210 sxs.cmt.

Aband. oil well _____, Gas well _____, Input well X, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____

Address: Russell, Kansas 67665

Company to plug at: Hour: 12:00 P.M. Day: 1 Month: February Year 2000

Plugging proposal received from: Dennis Roberts

Company: Dennis F. Roberts Phone: 785-625-8526

Were: Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.
4 1/2" casing set at 4109' w/175 sxs cement. Perf. 3882' - 3991'.
D.V. Anhy. At 2257' cemented with 500 sxs . Cement did not circulate.
Perf casing at 1100' and circulate to surface with 475 additional sxs.
Tubing fish at 3200'. T.O.F. at 1300'.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:30 P.M., Day 1, Month: February, Year: 2000

Actual plugging report: Ran W.H.M. to 3100'. Rigged up cementers to 4 1/2" casing. Took fluid rate at 3-4 bbls per minute on vacuum. Pumped in 200 sxs cement with 400# hulls to load casing. Max. P.S.I. 800#. S.I.P. 400#. Job complete.
Cement to surface in annulus.

Remarks: _____
Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____ CASING X Elevation: _____ G.L. _____

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED
DATE 2/15/00
INV. NO. 061253

RECEIVED Form CP-2/3
STATE CORPORATION COMMISSION

FEB 15 2000

CONSERVATION DIVISION
Wichita, Kansas

R