

9-6

293

R

6-070955

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21.017-0000  
SW NW NE /4 SEC. 3 , 10 S, 26 W  
4290 feet from S section line  
2310 feet from E section line

Operator license# 4629 Lease Zeigler well # 1-3

Operator: Brito Oil Co. Inc. County Sheridan 76.37

Address: 200 E. First #208 Well total depth 2350 feet  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Paul F. Brito Surface pipe 8 5/8 Inch @ 241 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Blue Goose Drilling License# 5104

Address: Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 6th Month: September Year: 91

Plugging proposal received from: Martin Miller

Company: Blue Goose Drilling Phone: 316-263-8787

Were: B 5/8" 241' S.P. cvc. w/150 sx. 60/40 poz. - 2% gel. -  
3% cal.cl. (By Allied). Elv. 2603' - Anhy. 2250' - No cir. problems.  
Mud cond. 46 vis. - 8 weight. Proposal 190 sx. 60/40 pozmix - 6% gel. -  
3% cal.cl. Spot with drill stem, circulate, heavy mud between all plugs.  
25 sx. @ 2280' - 100 sx. and 1 sx. F.C. @ 1328' - 40 sx. @ 290' -  
10 sx. @ 40' - 15 sx. rathole circulate.

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 4:00P.M., Day: 6th, Month: Sepeetmeber, Year: 91

Actual plugging report: Brito ordered 190 sx. 60/40 poz. - 6% gel. -  
3% cc. Spotted and displaced cement with drill stem. Circulated hole.  
1st plug @ 2280' w/25 sx. cement.  
2nd plug @ 1328' w/100 sx. cement w/1 sx. flocele.  
3rd plug @ 290' w/40 sx. cement.  
4th plug @ 40' w/10 sx. cement.  
15 sx. in Rathole (circulate)

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 8 1991  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Cement by: Allied.

INVOICED

DATE 10-11-91  
INV. NO. 33343

*John S.*

*Marion J. Schmidt*  
(agent)  
Form CP-2/3

I [ ] did not [ ] observe the plugging.