

4-18-88

6 061486

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,919-0000

NW, SEC 12, T 10 S, R 26 W3

3630 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5669

Lease Name Bittel Well # 1

Operator: Helberg Oil Co.  
Name & Address: Box 32

County Sheridan 130.00

Well Total Depth 4000 feet

Morland, Ks. 67650

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 209 w/135 sks

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Helberg Oil Co. License Number \_\_\_\_\_

Address Morland, Ks. 67650

Company to plug at: Hour: 1:00PM Day: 18 Month: April Year: 19 88

Plugging proposal received from Jerry M. Helberg

(company name) Helberg Oil Co. (phone) 913-627-5665

were: Order 180 sx 60/40 pozmix, 6% gel, 3% cc, lsk flocele and 8 5/8" plug. Spot with drill pipe with no less than 36 vis mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:00PM Day: 18 Month: April Year: 19 88

ACTUAL PLUGGING REPORT

1st Plug @ 2200' w/ 20 sx

2nd Plug @ 1300' w/ 100 sx

3rd Plug @ 250' w/ 40 sx

4th Plug @ 40' w/ 10 sx

10 sx in rat hole

Remarks: Cemented by B. J. Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-7-88

INV. NO. 21222

Signed Gilbert G. Scheck (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 7-6-88

CONSERVATION DIVISION Wichita, Kansas