

9-1-87 15-179-00120-0000

6 030934

API NUMBER 15- 3 - 17 - 55

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NW SE, SEC. 12, T 10S, R 26 W/E

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Custer Well # 1

Operator: John O. Farmer

County Sheridan 132.93

Name & Address Box 352

Well Total Depth 4090 feet

Russell, Kansas 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 145

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Eng. License Number 5111

Address Great Bend, Ks.

Company to plug at: Hour: PM Day: 1 Month: Sept Year: 19 87

Plugging proposal received from Deacon

(company name) Rockhold (phone)

were: 8 5/8" set at 145' w/145 sks, 5 1/2" set at 4089' w/125 sks.

Perf 3982' - 85'; Order sand and Common Cement.

Pull pipe. Order 200 sks A.T.L. Cement Blend 65/35 Pozmix 10% Gel 2% Dical and 6 sks/Hulls. Allied Cement Co. Walker Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30 PM Day: 1 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3930' w/5 sks Common Cement on sand w/bailer.

7 shots at 3000' 2000' 1800' 1600' 1400' 1200' and 1000'.

Recovered 1000' of 5 1/2 casing.

Squeezed down 8 5/8" 6 sks Hulls in with 200 sks Alt. Cement Blend

Max Psi. 400#. Close in Psi 150#. Plug complete.

RECEIVED CONSERVATION COMMISSION SEP 25 1987

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 9-28-87

INV. NO. 18281