

DEC 13 1986

6 030843

API NUMBER 15-179-20,879-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

155' SW OF  
NENE NE, SEC. 12, T 10 S, R 26 W

4840 feet from S section line

440 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5663

Lease Name MADER Well # 1

Operator: HESS OIL CO.

County SHERIDAN 131.30

Name & Address P.O. Box 905

Well Total Depth 4040 feet

MCPHERSON, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67460

Surface Casing: Size 8 5/8 feet 266'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor MAILLARD INC. License Number 4958

Address MCPHERSON KANSAS

Company to plug at: Hour: AM Day: 13 Month: 12 Year: 19 86

Plugging proposal received from ARNIE HESS

(company name) HESS OIL CO. (phone) \_\_\_\_\_

were: 8 5/8 SET @ 266' w/ 150SX. CIRCULATE HOLE BOTTOM TO TOP  
w/ NO LESS THAN 36 UIS. MUD MAINTAIN MUD @ SURFACE w/ NO LOSS  
OR GAIN. ORDER 200SX. 60/40 P2 6 PACE 1 3 PCC 8 5/8 W.P.  
ALLIED CNT. Co. BALANCE ALL PLUGS WITH MUD.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:AM Day: 13 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT SPOT D.P. @ 2175' DISPLACE 25SX. CNT. MIX.

LAYDOWN D.P. TO 1250' DISPLACE 100SX. CNT. MIX. w/ 15X. HULLS

LAYDOWN D.P. TO 300' DISPLACE 40SX. CNT. MIX. LAYDOWN D.P.

ADJUST MUD IN HOLE TO 40' PUSH W.P. TO KELLY DEPTH LOAD

HOLE TO BASE OF CELLAR w/ 10SX. CNT. MIX. DISPLACE w/ 10MT OF

PIPE 15SX. IN RATHOLE. 10SX. IN MOUSE HOLE. PLUG COMPLETE

Remarks: ANY. 2154-93 ELEV. 2531' GL.

**INVOICED**

(did, did not) observe this plugging.

DATE 1-7-87

INV. NO. 15836

Signed Carl Goodrow  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
1-7-87  
JAN 7 1987  
CONSERVATION DIVISION  
Wichita, Kansas