

7-10 159

To: 6 070851  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,967-0000  
approx 100' E of NW NW SW, SEC. 14, T. 10 S, R. 26 W/E

2310 feet from S section line  
4850 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Werth Well # 1-14

Operator: Chief Drilling Co. Inc.  
Name & Address: 224 E. Douglas #530  
Wichita, Ks. 67202

County Sheridan 133.41

Well Total Depth 4105 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number

Address Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 10 Month: July Year: 19 90

Plugging proposal received from Marion Burris

(company name) Warrior Drilling Co. (phone)

were: 8 5/8 260 s.p cwc/170 sks 60/40 poz 3% gel 2% ca cl. By Allied.

Elev. 2588. Anhy 2222. K.C. Well, no cir problems. Mud condition

44 vis. 9.1 weight 10 water loss. Proposal 200 sks 60/40 poz 6% gel w/1 sk

f.c. i. 25 sks w/w.p. at 40 ft. 15 sks in rathole cir. 10 sks mousehole.

(cir).

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour 6:00PM Day 10 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Chief ordered 200 sks 60/40 poz 6% gel 1 sk f.c. and 8 5/8

plug. Spotted cement through drill stem, heavy mud between all plugs.

1. 25 sks at 2235. 3. 40 sks at 300.

2. 100 sks w/1 sk f.c. at 1310. 4. 10 sks w/wiper plug at 40.

15 sks in rathole cir.

10 sks in mousehole cir

Remarks: Cemented by Allied.

RECEIVED  
7-20-90  
JUL 20 1990

INVOICED (If additional description is necessary, use BACK of this form.)

DATE 7-27-90

INV. NO. 28776

Gil S.

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt  
FORM CP-2/3  
Rev. 01-84