

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20302-00-00
Spot: CSWNENE Sec/Twnshp/Rge: 14-10S-26W
4290 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: WILLSON Well Number: 1
County: SHERIDAN Total Vertical Depth: 4070 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 252
Production: Size 5.5 feet: 4070
Liner: Size _____ feet:

\$132.28

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2001 11:00 AM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 10 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/09/2001 1:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 252' w/150 sxs cwc. 5 1/2" set at 4070' w/200 sxs.
Casing squeezes N/A - cement in braden head at surface.
Prod Perfs CIBP at 3900' and 4036' - open perf 3854' - 3865'.
Fluid level at about 3800'.
Filled 5 1/2" casing with 10 yards Redi-Mix (13 yards by yield)
Plug complete.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 1 2001

CONSERVATION DIVISION

INVOICED
DATE 5-01-01
INV. NO. 2001061741

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

HINKLE OIL COMPANY

#1 WILLSON

14-10-26W

WICHITA, KANSAS

SW NE NE

CONTR JOHN O. FARMER, INC.

CTY SHERIDAN

GEOL ORVIE HOWELL

FIELD WILLSON DISC.

E 2576 KB cm 2/13/71 ^{CARD} ISSUED 2/3/72 IP P 141 BOPD + TR WTR

LKC 3854-56 & 3863-65
GR 40

| | | | | | |
|--|--|--|--|--|--|
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

API 15-179-20 ³⁰² 295

| LOG | TOPS | DEPTH | DATUM | |
|--------|------|-------|-------|---|
| | | | | 8 5/8" 252/150sx; 5 1/2" 4071/200sx |
| ANHY | 2194 | + 382 | | DST(1) 3795-3838/30-30-60-30, 130'GSY OCM, 120'VSO |
| B ANHY | 2234 | + 342 | | WM, BHP 1028-974#, FP 27-152# |
| TOP | 3573 | - 997 | | DST(2) 3845-75/30-30-60-30, GA/30" TSTM. 2620'FL, |
| HEEB | 3787 | -1211 | | 2500'GSY OIL, 120'FRSAY OIL (GR 40), BHP 1251- |
| TOR | 3808 | -1232 | | 1239#, FP 11-989# |
| LANS | 3826 | -1250 | | DST(3) 3889-3915/30-30-60-30, 900'MSW, BHP 1260- |
| BKC | 4058 | -1482 | | 1239#, FP 54-889# |
| RTD | 4070 | -1494 | | DST(4) 3948-3993/30-30-60-30, 175'WCM, BHP 1322-1289 |
| LTD | 4072 | -1496 | | FP 35-89# |
| | | | | DST(5) 3991-4060/30-30-90-30, 120'GIP, 300'HO&GCM, |
| | | | | 50'GSY OCMW, BHP 1319-1278#, FP 45-179# |
| | | | | MCT, CO TO 4057 NFN, PF 8/4046-48, 500MCA & 1000 |
| | | | | REG, REC LD, SWB 6.72 BFPH 50% W/5HRS, FU 2250'FL/ |
| | | | | 12HRS, PF 8/4027-29, RBP @ 4035, SWB DWN & SWB 4.8 |
| | | | | BFPH 60% WTR/7HRS, FU 800'FL/12HRS, RBP @ 4020, PF |
| | | | | 8/4008--10, SWB DWN & SWB 6.2 BFPH 23% WTR/2HRS, A500 |
| | | | | (OVER) |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

14-10-26W
SW NE NE