

15-179-20921-00-00
4-28
394R

6 040961

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,912
SW SW SE SEC. 2 , T 10 S, R 26 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

330 feet from S section line

1650 feet from E section line

Operator: Energy Exploration

Lease Name M. J. Werth Well # 3

Name & Address 1002 S. Broadway

County Sheridan 133.25

Wichita, Ks. 67211

Well Total Depth 4100 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 228' w/150

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling License Number

Address Wichita, Ks.

Company to plug at: Hour: 9:00 PM Day: 28 Month: April Year: 19 88

Plugging proposal received from Dick Davis

(company name) H-30 (phone)

were: Order 190 sks cement + 60/40 Poz 6% Gel w/1/2 F.C.

Heavy mud between all plugs

Pump cement down drill pipe

Elev. 2554' Anhydrite 2175' - 2214'

Top Dakota 1575'

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1988

11-8-1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00PM Day: 28 Month: April Year: 1988

ACTUAL PLUGGING REPORT 25 sks at 2200' Anhy

100 sks at 1275'

40 sks at 260'

10 sks at 40'

15 sks in rathole.

Remarks: B. J. Titan Cementing Co.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

DATE 11-9-88

INV. NO. 22947

Signed Dennis L. Hamel (TECHNICIAN)
Dennis L. Hamel