

To: 6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Operator: Viking Resources
Name & Address: 120 S. Market
Wichita, Ko.

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated _____

Plugging Contractor Mallard License Number 4958
Address McPherson

Company to plug at: Hour: _____ Day: 18 Month: Oct Year: 19 88

Plugging proposal received from Arnie Hess

(company name) Mallard

were: Order 200 sks cement 60/40 Poz 6% Gel and 2 sks F.C.

Heavy mud between all plugs
Pump cement down drill pipe

Elevation 2587' Anhydrite 2216' - 51'

To Dakota 1550'

1037' - 1337' Plugging Proposal Received by D.F.B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:00AM Day: 18 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT
25 sks at 2240'
100 sks at 1340'
40 sks at 360'
10 sks at 40'
15 sks in rathole 10 sks in mousehole

Remarks: Allied Cementing Co.
(If additional description is necessary, use BACK of this form.)

I (operator) did not observe this plugging.

INVOICED

DATE 11-10-88

INV. NO. 22980

10-18 15-179-20931-00-00 28

API NUMBER 15- 179-20,931
SW 2, SEC. 2, T 10 S, R 26 W/E
990 feet from S section line
2970 feet from E section line

Lease Name Jon Lintel Vonfeldt Well # 3

County Sheridan

Well Total Depth 4071 132.31 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 335

(phone)
RECEIVED
STATE CORPORATION COMMISSION
11-8-1988
NOV 8 1988
CONSERVATION DIVISION
Wichita, Kansas

Signed Dale F. Balthazor
Dale F. Balthazor (TECHNICIAN)