

JAN 17 1987 15-179-20882-00-00

6 030851

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20,882

SUSSESE SEC. 2, T 10 S, R 26 (W)P

330 foot from S section line

990 foot from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Loose Name HAROLD WERTH Well # 1

Operator: DIAMOND SHAMROCK EXP CO, County SHERIDAN 133.25

Name & Address P.O. Box 400

Well Total Depth 4100 feet

AMARILLO, TEXAS

Conductor Pipe: Size _____ feet

79188-0001

Surface Casing: Size 8 7/8 feet 345'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor MURFIN DRIG. License Number 6033

Address WICHITA, KANSAS

Company to plug at: Hour: 9 PM Day: 17 Month: 1 Year: 19 87

Plugging proposal received from PETE COATS

(company name) _____ (phone) _____

were: 8 7/8 SET @ 345' w/230x. CIRC. HOLE FROM BOTTOM w/NO
LESS THAN 36 VIS. MUD. SPOT CMT. PLUGS w/ DRILL PIPE BALANCE
ALL PLUGS w/ MUD MAINTAIN FLUID LEVEL @ SURFACE w/NO LOSS
OR GAIN. ORDER 8 7/8 W.P. 190SX. 60/4002-6 7/8 GEI. 3 BCC HALLIBURTON
CMT. CO.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3 PM Day: 17 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT SPOT D.P. @ 2200' DISPLACE 25 SX. CMT. MIX

LAY DOWN D.P. TO 1250' DISPLACE 100 SX. CMT. MIX + 1 SX. HULLS

LAY DOWN D.P. TO 400' DISPLACE 40 SX CMT MIX. LAY DOWN

D.P. ADJUST FLUID IN HOLE TO KELLY DEPTH (40') PUSH

WIPER PLUG. TO KELLY DEPTH FILL HOLE TO BASE OF CELLAR

w/10 SX CMT. MIX. CIRCULATE RAT HOLE w/15 SX. CMT MIX. WITH JOINT

Remarks: Plug Comp. /

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
JAN 30 1987

INVOICED

DATE 2-2-87

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 16041