

1 031297

10-11

API NUMBER 15-033-20,476-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SE SW, SEC. 10, T 33 S, R 20 W  
660 feet from S section line  
1980 feet from W & section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145

Lease Name Box Ranch "B" Well # 1

Operator: Roberts & Murphy, Inc.

County Comanche

Name & Address P.O. Box 7125

Well Total Depth 5651 183.65 feet

Shreveport, LA 71137-7125

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 694

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 11 Month: 10 Year: 1994

Plugging proposal received from Robert Moorehead

(company name) Roberts & Murphy, Inc. (phone) 316-672-7737

logs: 4 1/2" at 5651' w/275 sx cement, PBTD 5580', Perfs at 5530-33'

1st plug set CIBP at 5500' and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 11 Month: 10 Year: 1994

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5500' and dumped 2 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 125 sx cement.

Maximum pressure 700 psf and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3297' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / observe this plugging.

DATE 11-3-94

Signed Steve Durant (TECHNICIAN)

INV. NO. 41577

RECEIVED  
STATE CORPORATION COMMISSION  
10-18-94  
OCT 18 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS