

To: 1 031296 10-11
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,708-0000
SW NE SW, SEC. 11, T 35 S, R 20 W
1825 feet from S section line
3580 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4145

Lease Name Box Ranch Well # 2-11
County Comanche

Operator: Roberts & Murphy, Inc.
Name & Address P.O. Box 7125
Shreveport, LA 71137-7125

Well Total Depth 5950 193.37 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 875

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:30 p.m. Day: 11 Month: 10 Year: 1994

Plugging proposal received from Robert Moorehead

(company name) Roberts & Murphy, Inc. (phone) 316-672-7737

Remarks: 5 1/2" at 5950' w/275 sx cement, Perfs at 5328-52, 5378-5404, CIBP at 5310, Perfs at 5284-90'

1st plug set CIBP at 5250' and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:40 p.m. Day: 11 Month: 10 Year: 1994

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5250' and dumped 2 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3250' of 5 1/2" casing.

If additional description is necessary, use BACK of this report.

Observe this plugging.

INVOICED

DATE 11-3-94

INV. NO. 41576

Signed Steve Durrant (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 10-18-94 OCT 18 1994