

To: I 090050  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-4

API NUMBER 15- 033-20,717 - 0001  
SW SW SW, SEC. 2, T 35 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145

450 feet from S section line  
4830 feet from E section line

Operator: Roberts & Murphy, Inc.  
Name & Address: P.O. Box 7125  
Shreveport, LA 71137-7125

Lease Name Box Ranch Well # 1-2  
County Comanche 227.50  
Well Total Depth 7000 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 832

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:35 p.m. Day: 4 Month: 2 Year: 19 91

Plugging proposal received from Monty  
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 6983' w/375 sx cement, PBSD 6251', Perfs at 6222-32',  
1st plug pump 1 sx hulls and 25 sx cement to 6000',  
2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,  
release 8 5/8" wiper plug and pump 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
2-6-91  
FEB 6 1991  
CONSERVATION DIVISION  
Middleton  
(TECHNICIAN)

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 4 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement to 6000',  
2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 5 sx gel, 100 lbs. hulls and  
150 sx cement.

Maximum pressure 1000 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 4000' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed [Signature]  
(TECHNICIAN)

INVOICED  
DATE 2-27-91  
INV. NO. 30936