

To: 1 060166  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION S/2 SW NW SW,  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-13 API NUMBER 15- 033-20,732-00-01  
2 SEC. 2, T. 35 S, R 20 W/E  
1350 feet from S section line  
330 feet from W E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4145  
Operator: Roberts & Murphy, Inc.  
Name &  
Address P.O. Box 7125  
Shreveport, LA 71137-7125

Lease Name Box Ranch Well # 2-2  
County Comanche 211.25  
Well Total Depth 6500 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 860

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 p.m. Day: 13 Month: 5 Year: 19 93

Plugging proposal received from Robert Moorehead

(company name) Roberts & Murphy, Inc. (phone) 316-672-7737

were: 5 1/2" at 6478' w/150 sx cement, PBSD 6245'. Perfs at 6202-06, 6218-22'

1st plug set CIBP at 6150' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:10 p.m. Day: 13 Month: 5 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6150' and dump 2 sx cement on top,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 475 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
5-18-93  
MAY 18 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4290' 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If desired, check box) - observe this plugging.

DATE 5-20-93

Signed [Signature]  
(TECHNICIAN)

INV. NO. 37745