

1090688

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-033-20,736-0000
SW SW NW, SEC. 2, T 35 S, R 20 W/E
2700 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4145
Operator: Roberts & Murphy, Inc.
Name & Address P.O. Box 7125
Shreveport, LA 71137-7125

Lease Name Box Ranch Well # 3-2
County Comanche
Well Total Depth 6600 214.5⁰ feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 850

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:30 p.m. Day: 4 Month: 6 Year: 1996

Plugging proposal received from John
(company name) Pratt Well Service, Inc. (phone) 316-672-5901

work: 5 1/2" at 6479' w/150 sx cement, PBD 6408', Perfs at 6255-63'
1st plug set CIBP with 2 sx cement on top over perfs,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

 Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 4 Month: 6 Year: 1996

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5250' with 2 sx cement on top,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

Maximum pressure 900 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4380' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-25-96
INV. NO. 45869

RECEIVED JUN 9 1996
KANSAS CORP CO. observe this plugging
Signed [Signature] (TECHNICIAN)

RECEIVED
KANSAS CORP CO.
JUN 12 1996
06-07-96