

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21, 394-00-00

NE SW - SW, Sec. 12, T 12 S, R 23 E

990 feet from N(S) section line

990 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name RIEDEL Well # 1

Operator: DAMAR RESOURCES, INC.

County TREGO

Name & Address: P.O. BOX 70
HAYS, KANS.
67601

Well Total Depth 4186 feet # 136.05

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRILLING, INC. License Number 5422 TAG # 182

Address 801 UNION CENTER, WICHITA, KANS. 67202

Company to plug at: Hour: 12:00 PM Day: 1st Month: JAN. Year: 1984

VERBAL PLUGGING RECOMMENDATIONS GIVEN TO BILL CRAIG.

(company name) ABERCROMBIE DRILLING, INC (phone) 913-625-0020

were: 8 5/8" 345 EI 5.0 CUL # / 345 SK CMT COMMON GEL-CH-CL (BY ALLIED)

ORDER 210 50/50 Pozmix 6% GEL-3% CH-CL, 2 SK CELLO FLAKE AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS.
NO SHOW, BLOW, OR CIRCULATION PROBLEMS.

ARBUCKLE 4150 - ELY. 2437 - ANN. 1855.

Signed [Signature] (TECHNICIAN) 201C

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 PM Day: 1st Month: JAN. Year: 1984

ACTUAL PLUGGING REPORT

ORDERED 210 50/50 Pozmix 6% GEL-3% CH-CL, 2 SK CELLO FLAKE + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - TURNED HOLE OVER, HEAVY MUD BETWEEN PLUGS

1st Plug @ 4150 EI # / 20 SK CMT. 2nd Plug @ 1860 EI # / 20 SK CMT.

3rd Plug @ 1050 EI # / 100 SK CMT. 4th Plug @ 350 EI # / 50 SK CMT.

5th Plug SOLID BRIDGE HULL'S - PLUG @ 40 EI # / 0 SK CMT., 10 IN RAT HOLE (CIRCULATE)

Remarks: CEMENTED BY ALLIED CMT. [2 SK CELLO-FLAKE IN CEMENT]

I hereby certify that the above plugging instructions were given as herein stated and that I () / did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed [Signature] (TECHNICIAN) 201C

DATE 1-13-84

INV. NO. 9079W

JAN 09 1984
01-09-1984
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 9-82