

To: 1 090687
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15-033-20,755-0000
SW NE NE, SEC. 3, T 35 S, R 20 XX
4290 feet from S section line
1000 feet from E section line

Operator License # 4145
Operator: Roberts & Murphy, Inc.
Name & Address: P.O. Box 7125
Shreveport, LA 71137-7125

Lease Name Box Ranch Well # 3-3
County Comanche
Well Total Depth 6550 ^{212.87} feet
Conductor Pipe: Size 20 feet 68
Surface Casing: Size 8 5/8 feet 850

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 4 Month: 6 Year: 1996

Plugging proposal received from John
(company name) Pratt Well Service, Inc. (phone) 316-672-5901

Work: 5 1/2" at 6457' w/175 sx cement, PBSD 6375', Perfs at 6214-24, 6232-41'
1st plug set CIBP with 2 sx cement on top over perfs,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 4 Month: 6 Year: 1996

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5250' with 2 sx cement on top, 6-7-96

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Maximum pressure 900 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4357' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-25-96
INV. NO. 45870

RECEIVED
KANSAS CORP COMM
Signed

[Signature]
(TECHNICIAN)

RECEIVED
KANSAS CORP COMM
JUN 7 1996
P 12:10