

To: 1 052141 6-17
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API-NUMBER 15- 033-20,786 -0000
NE SW NW NE, SEC. 3, T 35 S, R 20 ~~XX~~
870 feet from ~~5~~ section line
2200 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145
Operator: Roberts & Murphy, Inc.
Name & Address: P.O. Box 7125
Shreveport, LA 71137-7125

Lease Name Box Ranch Well # 4-3
County Comanche 211.25
Well Total Depth 6500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 666

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 17 Month: 6 Year: 19 97

Plugging proposal received from Kenny Gates
(company name) Pratt Well Service (phone) 316-672-5901

were: 4 1/2" at 6436' w/150 sx cement, PBSD 6364', Perfs at 6207-21'
1st plug set CIBP at 6000' with 2 sx cement on top,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None
Operations Completed: Hour: 10:55 a.m. Day: 17 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6000' with 2 sx cement on top,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 450 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4195' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE JUN 23 1997
INV. NO. 48387
6-17

6-20-97 RECEIVED
KANSAS CORP. CO. INC.
SIGNED Richard M. Lacey (TECHNICIAN)