

RECEIVED

JUN 27 2003

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

15-033-1900-00-00 (PLEASE TYPE FORM and File ONE Copy)

API # 15-033-20719 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Roberts and Murphy, Inc. KCC LICENSE # 4145

ADDRESS Post Office Box 7125 (owner/company name) CITY Shreveport (operator's)

STATE Louisiana ZIP CODE 71137-7125 CONTACT PHONE # (318) 221-8601

LEASE Box Ranch B WELL# B-2 SEC. 10 T. 35S R. 20W (East/West)

- E2 - SE - SE SPOT LOCATION/0000 COUNTY Comanche

1270 FEET (in exact footage) FROM (S/N (circle one) LINE OF SECTION (NOT Lease Line)

510 FEET (in exact footage) FROM (E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 639' CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5475' CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5393-5397', 5403-5418'

ELEVATION 1768'/1771' T.D. 5640 PBTD 5475 ANHYDRITE DEPTH 5465'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE X

PROPOSED METHOD OF PLUGGING Set CIBP @ 5400 and dump bail 2 sks cement, cut 4 1/2"

casing @4750' and pull casing. Pump down 8 5/8" casing: 300# Hulls; 10 sks gel;

50 sks cmt; 10 sks gel; 100# Hulls; 150 sks cmt, dump down 8 5/8" surf-10 ft cmt.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? Log previously submitted

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ken Frazier PHONE# (318) 458-2911

ADDRESS Post Office Box 7125 City/State Shreveport, LA 71137-7125

PLUGGING CONTRACTOR Key Energy Services KCC LICENSE # 33223

ADDRESS P.O. Box 1273, Liberal, KS 67905-1273 PHONE # () 620-624-7235

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Rig availability, will notify KCC of date

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6/24/03 AUTHORIZED OPERATOR/AGENT: Bruce S Roberts
(signature)

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Roberts and Murphy, Inc.
PO Box 7125
1500 N. Market
Shreveport, LA 71137-7125

June 27, 2003

Re: BOX RANCH #B 2
API 15-033-~~20719-00-01~~ ¹⁹⁰⁰¹⁻⁰⁰⁰⁰ RT KCC
E2SESE 10-35S-20W, 1270 FSL 510 FEL
COMANCHE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888