

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-195-21,684-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Energy Three Inc. OPERATORS LICENSE NO. 5430

ADDRESS Box 1505, Great Bend, Kansas 67530 PHONE # (316) 792-5968

LEASE (FARM) Rhoden WELL NO. 1 WELL LOCATION SE NW NE COUNTY Trego

SEC. 14 TWP. 12 RGE. 23 (E) or (W) (W) TOTAL DEPTH \_\_\_\_\_ PLUG BACK TD 4193'

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8 SET AT 265 CEMENTED WITH 175 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL \_\_\_\_\_

1st plug @ 1900' w/ 20 sxs 2nd plug @ 1100' w/100 sxs 1 sx flowseal 3rd plug @ 300' w/40 sxs

4th plug @ 40' solid bridge w/10 sxs to surface rathole 10 sx mousehole 10 sx total 190 sx  
50/50 poz 6% gel 3% cc (If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? \_\_\_\_\_  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3-30-85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Stan Lovelady PHONE # (913) 637-5487

ADDRESS Box 52, Gorham, Kansas 67640

PLUGGING CONTRACTOR Big Three Drilling Inc. LICENSE NO. 8836

ADDRESS Box 52, Gorham, Kansas 67640 PHONE # (913) 637-5487

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Timothy F. Scheck  
(Operator or Agent)

DATE: April, 11, 1985

RECEIVED  
STATE CORPORATION COMMISSION  
APR 15 1985  
04-15-1985  
CONSERVATION DIVISION