

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
12-05-1973
DEC 5 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 435 Page Court, 220 West Douglas, Wichita, Kansas.

Lease Name: Deines Well No. 1

Location: SW-^{NE}~~NW~~-SE ^{ANB}~~YCC~~ Sec. 26 Twp. 12 Rge. (E)(W) 23

County: Trego Total Depth 4457' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

247'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 625'.

Circulate hole with heavy mud. Pull DP to 850' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Doherty

Conservation Division Agent